

SCHEDULE "A"

Schedule "A" attached to and a part of that certain chattel mortgage in which
 WIND RIVER VENEER, INC., appears as mortgagor and C.I.T. CORPORATION as
 mortgagee dated July 29, 1963
R.M.C.

DESCRIPTION OF EQUIPMENT

Item No.	Unit No.	Type and Description
----------	----------	----------------------

CLASS I: VENEER MILL EQUIPMENT

1 1 Transfers to Lathe

One (1) Log haul and transfer system from pond to veneer lathe.

Log Haul

One (1) 2-chain and chair lift type log transfer with chains set 6' apart on 6" channel chainways on 12" I-beam stringers, 48' long with tail section hinged, 4" pitch riveted chain, 3 7/16" head shaft, 2 timber end pile support bents, 4 pile and timber supports for tail section with link chain hangers, motorized with 1 3/4" roller chain and V-belt through Link-Belt worm gear reducer.

First Deck Section

One (1) 60' long 2-chain transfer with #C-13L combination chains set 5' apart on 5" channel chainways on 12x12" timber stringers on 8 - 12x12" timber support bents and pile caps on 3 piling bases, 3 7/16" head shaft, roller chain drive from 7 1/2 H.P. Pacific gearmotor.

Second Deck Section

One (1) 18' Long 2-chain transfer with 10" WF beam stringers and supports, drive by 7 1/2 H.P., 30 R.P.M. Pacific Gearmotor #15RA-8372 with wiring.

Third Deck Section

One (1) 22 1/2' Long 2-chain transfer similar to second section with 2 air operated jump arm log stops, drive by 5 H.P., 48 R.P.M. Broma gearmotor unit.



PAGE 1 OF 9 Pages

DATE OF CONTRACT	1963
SHIPPING PORT	Seattle
COMMENCING DATE	1963
COMPLETION DATE	1964
CAPACITY =	1000
MANUFACTURER	W.W. Gandy
VENeer	1000
WATER	1000
WOOD	1000
STEEL	1000
IRON	1000
ALUMINUM	1000
PLASTIC	1000
GLASS	1000
WOOD	1000
IRON	1000
STEEL	1000
ALUMINUM	1000
PLASTIC	1000
GLASS	1000