SCHEDULE "A"

Schedule "A" attached to and a part of that certain chattel mortgage in which WIND RIVER VENEER, INC., appears as mortgagor and C.I.T. CORPORATION as mortgagee dated J. 6, 1963

DESCRIPTION OF EQUIPMENT

Item No.	Unit No.	Type and Description
		CLASS I: VENEER MILL EQUIPMENT
1	1	Transfers to Lathe

One (1) Log haul and transfer system from pond to veneer lathe.

Log Haul
One (1) 2-Chain and chain lift type log transfer with chains set 6' apart on 6" channel chainways on 12" I-beam stringers, 48' long with tail section hinged, 4" pitch riveted chain, 3 7/16" head shaft, 2 timber and pile support bents, 4 pile and timber supports for tail section with link chain hangers, motorized with 1 3/4" roller chain and V-belt through Link-Belt worm gear reducer.

First Deck Section
One (1) 60' long 2-chain transfer with #C-131 combination chains set 5' apart on 5" channel chainways on 12x12" timber stringers on 8 - 12x12" timber support bents and pile caps on 3 piling bases, 3 7/16" head shaft, roller chain drive from 7½ H.P. Pacific gearmotor.

Second Deck Section
One (1) 18' Long 2-chain transfer with 10" WF beam stringers and supports, drive by 7½ H.P., 30 R.P.M. Pacific Gearmotor #15MA-8372 with wiring.

Third Deck Section
One (1) 22½' Long 2-chain transfer similar to second section with 2 air operated jump arm log stops, drive by 5 H.P., 48 R.P.M. Emma gearmotor unit.

Unofficial Copy