

SCHEDULE "A" - DESCRIPTION OF EQUIPMENT
(continued)

Item No.	Unit No.	Type and Description
7	7	One (1) Edger unit with following: Edger One (1) 48" Schurman 5-saw stub edger, serial #337, arranged with extended base and coupling for direct motor drive, feed drive from main arbor with Drive-All transmission, air lift (1) press rolls, kick-back fingers. Shifter One (1) Portland Iron Works 4-saw shifter unit, order #5151, date 3/28/61; air operated increment type, predetermined set, solenoid valve control with operator console Motor One (1) 100 H.P., 1760 R.P.M., 220/440 V. Allis-Chalmers type AW ball bearing induction motor #20BS8-51-639-488-8. One (1) Manual starting compensator, 100 H.P. One (1) 2"x55' Conduit wiring lead with 4 factory elbows, 2 Type L condulets and 2"x3' flexible connection. Feed Table One (1) 27"x20' Steel frame 6-dead roll feed table with 4" rolls in 4" angle iron frame; with 3x22" live pipe jump roll set in table, hinged frame mount with manual jump linkage, roller chain and V-belt drive, motor and wiring; 4" angle iron guide fence length of table. Take-off Belt One (1) 48"x12' Belt conveyor take-off table behind edger with rubber belt, 15" steel end drums on 2 3/16" ball bearing shafts, 1 - 4" idler roll, steel table frame with 6" I-beam stringers and legs, plywood deck, 1" roller chain drive from worm gear speed reducer with V-belt drive by 3 H.P., 1740 R.P.M. motor, 1/2" conduit wiring.
8	8	Transfer to Trimmer One (1) 7-chain transfer system to trimmer in 3 sections with drop-out section to 7-chain transfer to chipper conveyor.