

SCHEDULE "A" - DESCRIPTION OF EQUIPMENT
(continued)

Item No.	Unit No.	Type and Description
13	13	Power Wiring

Main Panel

Two (2) 600 Amp., 600 V., 3-pole fused safety switches
One (1) 400 Amp., 600 V., 3-pole fused safety switch
Three (3) 200 Amp., 600 V., 3-pole fused safety switches
Three (3) 100 Amp., 600 V., 3-pole fused safety switches
Two (2) 60 Amp., 600 V., 3-pole fused safety switches
Four (4) 30 Amp., 600 V., 3-pole fused safety switches

One (1) Size 3 magnetic starter
One (1) Size 2 magnetic starter
Three (3) Size 1 magnetic starters
One (1) Size 2 reversing magnetic starter
One (1) 4x4" - 4' Steel wiring gutter
One (1) 6x6" - 6' Steel wiring gutter
One (1) Set 2 - 4"x2' conduit wired leads with type FE condulets to main switches and 3-wire open pole line from transformers near shop

Trimmer Subpanel

27' 1 1/2" conduit wiring from main panel
Two (2) 1 1/2" Factory elbows
One (1) 1 1/2" Type L conduit
One (1) 8x8" - 4' Steel wiring gutter
Five (5) 30 Amp., 575 V., 3-pole safety switches
One (1) Size 2 magnetic starter
Three (3) Size 1 magnetic starters
One (1) Size 1 reversing magnetic starter
Two (2) Push button stations
One (1) Welded angle support frame

Edger Subpanel

14' 1" Conduit wiring
One (1) 1" Factory elbow
One (1) 1" Type L conduit
One (1) 4x4" - 4' Steel wiring gutter
Five (5) 30 Amp., 575 V., 3-pole safety switches
Five (5) Size 0 magnetic starters
Three (3) Push button stations