

SCHEDULE "A"

Schedule "A" attached to and a part of that certain chattel mortgage in which HEGEWALD
TIMBER CO., INC. appears as mortgagor and C.I.T. CORPORATION as mortgagee dated
SEP 30 1965.

DESCRIPTION OF EQUIPMENT

STACKER UNIT

#1 - Stacker

One (1) Stacker unit as follows:

One (1) 18' - 4 chain transfer H78 chain, 12" I beam stringer 4" channel runner, 4x6" pulleys 10" sprockets, 2 15/16" - 20' shaft roller chain drive from 10 H.P., 30 R.P.M. 440 volt Master gearmotor.

One (1) 48" - 4 arm breakdown hoist roller chain operated by 10 H.P. 30 RPM, 440 volt Pacific gearmotor with 5" magnetic brake.

One (1) 4'6" chain transfer 4" channel runner H78 chain 10" sprockets, 2 15/16"x20' shaft roller chain and V belt drive from gearbox and 3 H.P., 1800 R.P.M. 440 volt G. E. induction motor.

One (1) 8 - 2' Rapid wheel transfer

One (1) Installation of 6 - 6x30" dead grooved pipe rolls, 6" channel stringer, roller chain drive by 5 H.P. 68 R.P.M. 440 volt Pacific gearmotor and triple roller chain end line-up unit.

One (1) 11' - 6 chain transfer same as 4'6" transfer.

One (1) Motorized concentric unit.

One (1) 11 Unit sticker machine

One (1) 6 Arm stacker unit with roller chain drive from gearbox and 7 1/2 H.P., 1200 R.P.M., 440 volt G. E. induction motor with 5" magnetic brake.

One (1) 16 - 8x48" 4' on center dead pipe rolls 8' ave. roller chain drive complete with 12" I beam stringers and 5 H.P. 36 R.P.M. 440 volt Pacific gearmotor

One (1) Wood operator's platform
Eight (8) Conduit wired connections