

HOME VALLEY VENEER UNIT - DESCRIPTION OF EQUIPMENT

Item No.	Type and Description
1	<p>Log Transfer</p> <p>One (1) 24' Long 2 chain log transfer from outside on way to Charger.</p>
2	<p>Log Transfer</p> <p>One (1) 28' Long 2 chain Transfer from #1 Transfer to Lathe Charger.</p>
3	<p>Lathe Charger</p> <p>One (1) Lathe Charger designed and built by Diamond Lumber Co. consisting of:</p> <ul style="list-style-type: none"> One (1) 26'6" Long, 2 chain log Transfer complete with chain, shaft, sprockets, bearing & roller chain drive. One (1) 2 Arm hydraulic operated log positioner with independent operated positioning arms, complete with self-contained 10 H.P., hydraulic pump unit, tank & pipe. Rack & pinion operated forward & reverse movement, complete with shaft, bearings, sprockets, etc. Four (4) Air operated stop pins with local pipe, & control. Complete with steel frame, hydraulic pipe & controls.
4	<p>Core Transfer</p> <p>One (1) 22' 6" Long 4 chain Core transfer at Lathe.</p>
5	<p>Core Kicker</p> <p>One (1) Local assembled 2 arm kicker on 4 1/2" - 2 3/16" shaft, complete with 12" hydraulic cylinder, pipe, controls, limit switch, etc.</p>
6	<p>Core Transfer</p> <p>One (1) 79' Long 2 chain Transfer to outside.</p>
7	<p>Lathe</p> <p>One (1) Series #40 Model #247 Coe 110" swing, 135" knife, 7" spindle full motorized veneer lathe with steady rest, 6 belt offbearing transfer, 15 H.P., 30 gallon hydraulic unit, Elford knife clamp, complete with local pipe, wire & operators control. Serial #48002.</p>